

Templating

Templating involves a site visit where a member of the Avon Marble staff will make a MDF representation of the required worktops. Prior to our visit, there are a few things we will require you to do in preparation. Firstly, the kitchen base units should be fixed, securely, level, true and in their final position. All related appliances should be on site ie hobs, sinks, taps, waste disposal switches and pop-up waste levers etc. Basically anything that will be fitted into the granite has to be on-site.

If you are having an under-mounted sink, it should be fitted in the sink unit prior to our visit. If you have a particular view on where the taps, drainer, hob or sink should be then please make it clear to our member of staff during the site visit. Proposed position of joins may be discussed during the visit but these are subject to changes caused by sheet sizes or extreme colour variation.

At this point our member of staff can advise you on any extra support or work that may need to be carried out by your carpenter/kitchen fitter. You will be given time between the templating and the installation to have this work carried out.

It is vital that the templating is carried out accurately. Therefore we would like to stress how important it is that all the kitchen units, end panels and any other furniture that will affect the way the granite is fitted should be fixed and in its final position prior to our templating visit.

Also, all appliances should be on site, these include hobs, sinks, taps, waste disposal, soap dispensers and brackets for breakfast bars. Basically, anything that will affect the worktops should be on site so we can check them to avoid any problems further down the line.

Any revisits to site after the templating, resulting from changes made as stated above will be subject to a new templating fee.